

ADDENDUM TO THE CONSTRUCTION OF KINDARUMA MUTUOVARE AND GITARU MATHIGIRA KENDA WATER SUPPLY SYSTEM TENDER NO. CGE/T/019/2018-2019

Please note a few changes in the above project:

Amendment No. 1

Bill ON CONSTRUCTION OF KINDARUMA MUTUOVARE ISSACO AND KARURA WATER SUPPLY SYSTEM						
Bill No.2 - Main Pipelines						
Item	Old Description	Amended Description	Unit	Quantity	Rate	Amount
2.2	Main Pipeline					
2.2.1	Excavation and backfilling in Soil for width 1.0m and for depth of 1m- (21,000M)	Excavation and backfilling in Soil for width 1.0m and for depth of 1M - 23,200M	M3	23,200		
2.3	PIPEWORK					
2.3.1	Supply, install and test HDPE pipe of diameter 90mm PN16 from Kindaruma to Mutuovare Market (8,000 M)	Supply, install and test UPVC Pipes of diameter 90mm PN16 (With Rubber Rings) From Gitaru Dam to Mutuovare Market (10,200M)	M	10,200		
2.3.2	Supply, install and test HDPE pipe of diameter 63mm PN16 from Mutuovare to Karura Market	Supply, install and test UPVC Pipes of diameter 63mm PN16 (With Rubber Rings) Mutuovare to Karura Market	M	7,000		
2.3.4	Supply, install and test HDPE pipe of diameter 63mm PN16 from Mutuovare to Issaco market	Supply, install and test UPVC Pipes of diameter 63mm PN16 (With Rubber Rings) Mutuovare to Issaco market	M	6,000		
2.9	Supply and install a pump of capacity 2.5lts at a head of 120m together with its control panel	Supply and install Centrifugal pump of Capacity 5litres/Second coupled with its 3 phase control Panel	No.	2		

Amendment No. 2

Bill ON CONSTRUCTION OF GITARU MATHIGIRA KENDA AND KABUGURI WATER SUPPLY SYSTEM						
Bill No.2 - Main Pipelines						
Item	Old Description	Amended Description	Unit	Quantity	Rate	Amount

4.3	PIPEWORK					
4.3.1	Supply, install and test HDPE pipe of diameter 63mm Pn16 from Gitaru to Mathigira Kenda market	Supply, install and test UPVC Pipes of diameter 90mm PN16 (With Rubber Rings) from Gitaru to Mathigira Kenda market	M	4,000		
4.3.2	Supply, install and test HDPE pipe of diameter 63mm Pn16. From Mathigira Kenda to Kabuguri Market	Supply, install and test UPVC Pipes of diameter 63mm PN16 (With Rubber Rings) From Mathigira Kenda to Kabuguri Market	M	1,000		
4.9	Supply and install a pump of capacity 2.5lts at a head of 120m together with Control Panel	Supply and install Centrifugal pump of Capacity 5litres/Second coupled with its 3 phase control Panel	No.	2		