

ADDENDUM TO THE CONSTRUCTION OF RIAKANAU MALIKINI, KIAGENI MWANYANI AND MBONDONI KITHECU WATER SUPPLY SYSTEM TENDER NO. CGE/T/020/2018-2019

Please note a few changes in the above project:

Amendment No. 1

Bill ON CONSTRUCTION OF KIAGENI MWANYANI WATER SUPPLY SYSTEM						
Bill No.2 - Main Pipelines						
Item	Old Description	Amended Description	Unit	Quantity	Rate	Amount
2.3	PIPEWORK					
2.3.1	Supply, install and test HDPE pipe of diameter 63mm PN16	Supply, install and test UPVC Pipes of diameter 63mm PN16 (With Rubber Rings)	M	4,000		
2.3.2	Supply, install and test HDPE pipe of diameter 63mm PN16	Supply, install and test UPVC Pipes of diameter 63mm PN16 (With Rubber Rings)	M	3,000		
2.9	Supply and install a pump of capacity 2.5lts at a head of 120m with control Panel	Supply and install Centrifugal pump of Capacity 5litres/Second coupled with its 3 phase control Panel	No.	2		

Amendment No. 2

Bill ON CONSTRUCTION OF RIAKANAU MALIKINI WATER SUPPLY SYSTEM						
Bill No.4 - Main Pipelines						
Item	Old Description	Amended Description	Unit	Quantity	Rate	Amount
4.3	Pipe Work					
4.3.1	Supply, install and test HDPE pipe of diameter 160mm PN16	Supply, install and test UPVC Pipes of diameter 160mm PN16 (With Rubber Rings)	M	14,000		
4.3.2	Supply, install and test HDPE pipe of Diameter 50mm, PN16.	Supply, install and test UPVC Pipes of diameter 63 mm PN16 (With Rubber Rings)	M	3,000		

Amendment No. 3

Bill ON CONSTRUCTION OF MBONDONI KITHECU WATER SUPPLY SYSTEM						
Bill No.6 - Main Pipelines						
Item	Old Description	Amended Description	Unit	Quantity	Rate	Amount
6.3	Pipe Work					
6.3.2	Supply, install and test HDPE pipe of Diameter 63mm, PN16.	Supply, install and test UPVC Pipes of diameter 90mm PN16 (With Rubber Rings)	M	14,000		
6.9	Supply and install a pump of capacity 2.5lts at a head of 120m with control panel	Supply and install Centrifugal pump of Capacity 5litres/Second coupled with its 3 phase control Panel	No.	2		