

PROJECT NAME: MAINTENANCE KARURUMO MARKET ACCESS ROADS					
CONSTITUENCY : RUNYENJE'S WARD: KYENI SOUTH					
Bill of Quantities					
ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
Note: No separate payments shall be made for the overhaul of material and the cost of such shall be included in the rates and or prices					
<b>BILL 1</b>	<b>PRELIMINARIES AND ADMINISTRATION OVERHEADS</b>				
01-60-005	Provide, install and maintain sign board throughout the contract period	NO	1	30,000	30,000
01-80-010	Prime Cost sum of Kshs. 25,000 for Material testing for specialised quality control test in accordance with clause 203 of the standard specification	PC SU M	1	25,000	25,000
01-80-011	Extra-over item Above (4) for contractor's overhead and profit	%	1		
Total Carried Forward to summary:					
<b>SITE CLEARANCE AND TOPSOIL STRIPPING</b>					
04-50-009	Soil stripping and cart to spoil	M <sup>3</sup>	1500		
Total Carried Forward to summary:					
<b>BILL 8</b>	<b>CULVERT AND DRAINAGE WORKS</b>				
08-60-025	Provide and install 600mm culverts including bedding, wing walls, approaches and haunching. Provide all the materials and erect headwalls to details including 150 mm concrete bed. Backfill along the sides and dispose of all excess materials	MT	35		
08-60-024	Provide and install 450mm culverts including bedding, wing walls, approaches and haunching. Provide all the materials and erect headwalls to details including 150 mm concrete bed. Backfill along the sides and dispose of all excess materials	MT	30		